



NOTES:

- ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321 - STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF FLEXIBLE THERMOPLASTIC SEWER PIPE, LATEST EDITION.
- SEE A-LOK FOR SPECIFIC PRODUCT INFORMATION AND SELECTION.
- A-LOK IS A REGISTERED TRADEMARK OF A-LOK PRODUCTS, INC. (WWW.A-LOK.COM)
- SEE STRUCTURE CONNECTION INSTALLATION DETAIL (D-2-109) FOR PROPER BACKFILLING TECHNIQUES NEAR STRUCTURES.

PIPE SIZE in (mm)	PVC ADAPTER OD in (mm)	A-LOK (P/N)
12 (300)	12.5 (318)	410
15 (375)	15.3 (389)	490
18 (450)	18.7 (475)	610
24 (600)	24.8 (630)	800
30 (750)	32.0 (813)	1040

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. © PRINSCO, INC.



1717 16TH ST. NE
WILLMAR, MN 56201
www.prinsco.com

TITLE: HP PIPE - STRUCTURE CONNECTION - A-LOK WITH PVC ADAPTER			REV: C
DRAWN BY: TSS	DATE: 17-Aug-17	DRAWING NUMBER: D-2-118	
SCALE: NTS	SHEET: 1 OF 1		