



NOTES:

- ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321 - STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF FLEXIBLE THERMOPLASTIC SEWER PIPE, LATEST EDITION.
- NON-SHRINK GROUT PROVIDES A SOIL TIGHT CONNECTION.
- SEE STRUCTURE CONNECTION INSTALLATION DETAIL (D-2-109) FOR PROPER BACKFILLING TECHNIQUES NEAR STRUCTURES.

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. © PRINSCO, INC.



1717 16TH ST. NE  
WILLMAR, MN 56201  
www.prinsco.com

TITLE:		HP PIPE - STRUCTURE CONNECTION - GROUT		REV:	B
DRAWN BY:	TRA	DATE:	30-Jun-17	DRAWING NUMBER:	
SCALE:	NTS	SHEET:	1 OF 1	D-2-110	