



NOTES:

- ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321 - STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF FLEXIBLE THERMOPLASTIC SEWER PIPE, LATEST EDITION.
- SEE Z-LOK FOR SPECIFIC PRODUCT INFORMATION AND SELECTION.
- Z-LOK IS A REGISTERED TRADEMARK OF A-LOK PRODUCTS, INC (WWW.A-LOK.COM)
- SEE STRUCTURE CONNECTION INSTALLATION DETAIL (D-2-109) FOR PROPER BACKFILLING TECHNIQUES NEAR STRUCTURES.

PIPE SIZE in (mm)	Z-LOK (P/N)
12 (300)	ZS-8016
15 (375)	ZS-8019
18 (450)	ZS-8022
24 (600)	ZS-8031
30 (750)	ZS-8039
36 (900)	ZS-8045

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. © PRINSCO, INC.



1717 16TH ST. NE
WILLMAR, MN 56201
www.prinsco.com

TITLE:	HP PIPE - STRUCTURE CONNECTION - Z-LOK		REV:	C
DRAWN BY:	TSS	DATE:	17-Aug-17	DRAWING NUMBER:
SCALE:	NTS	SHEET:	1 OF 1	D-2-119