



NOTES:

1. ALL PIPE SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321 - STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF FLEXIBLE THERMOPLASTIC SEWER PIPE, LATEST EDITION.
2. CONNECTIONS TO STRUCTURES CAN BE MADE IN A NUMBER OF WAYS DEPENDANT ON THE JOINT PERFORMANCE REQUIREMENTS AND INSTALLATION PRACTICES. STRUCTURE GASKET MUST BE UNIFORMLY FIT AROUND PIPE ADAPTER.
3. PROPER BACKFILL PROCEDURES MUST BE FOLLOWED TO PREVENT DIFFERENTIAL SETTLEMENT BETWEEN THE PIPE AND MANHOLE STRUCTURE.
4. JOINTS (E.G., BELL & SPIGOT, COUPLER, ETC.) 18"-36" (450-900mm) AWAY FROM STRUCTURE WALL IS PRESENTED AS A BEST PRACTICE DUE TO THE DIFFERENTIAL SETTLEMENT CONCERNS HIGHLIGHTED IN NOTE 3. THIS IS NOT A REQUIREMENT.

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. © PRINSCO, INC.



1717 16TH ST. NE
WILLMAR, MN 56201
www.prinSCO.com

TITLE: HDPE PIPE - STRUCTURE - INSTALLATION

DRAWN BY: SSB	DATE: 20-May-20	DRAWING NUMBER:
SCALE: NTS	SHEET: 1 OF 1	D-1-109