





Chamber Specifications				
Chamber Size (L x W x H)	51.8" x 100.5" x 59.5" (1,317 x 2,554 x 1,511 mm)			
Installed Length	48.3" (1,227 mm)			
Chamber Storage	109.6 ft <sup>3</sup> (3.10 m <sup>3</sup> )			
Min. Installed Storage*	164.5 ft <sup>3</sup> (4.66 m <sup>3</sup> )			
Weight / Chamber	112 lbs (50.80 kg)			
Chambers / Pallet	10			
Approx. Weight / Pallet	1,350 lbs (612 kg)			







End Cap Specifications				
End Cap Size (L x W x H)	35.0" x 94.0" x 59.3" (889 x 2,388 x 1,506 mm)			
Installed Length	32.4" (823 mm)			
End Cap Storage	39.6 ft <sup>3</sup> (1.12 m <sup>3</sup> )			
Min. Installed Storage*	114.46 ft <sup>3</sup> (3.10 m <sup>3</sup> )			
Weight	79.9 lbs (36.24 kg)			



\*ASSUMES 12" (300 mm) STONE ABOVE CHAMBERS/END CAPS, 9" (230 mm) OF STONE FOR FOUNDATION STONE, 9" (230 mm) OF STONE BETWEEN CHAMBERS/END CAPS, 12" (150 mm) OF STONE PERIMETER IN FRONT OF END CAPS AND 40% STONE POROSITY.

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. @ PRINSCO, INC.



1717 16TH ST. NE WILLMAR, MN 56201 www.prinsco.com

IIILE:	
	HYDROSTOR HS290 - SPECIFICATION

32.4" INSTALLED

DRAWN BY:	SLE	DATE:	27-Jul-22	DRAWING NUMBER:
SCALE:	NTS	SHEET:	1 OF 1	D-7-501