
SHOWN AS HARCO BASIN. SEE STRUCTURE OPTIONS FOR ALTERNATE CONFIGURATIONS HDPE BYPASS PIPE OUTLET SIDE SHOWN AS REDUCING WYE. SEE STRUCTURE OPTIONS FOR ALTERNATE CONFIGURATIONS SOIL-TIGHT OR WATERTIGHT COUPLER (TYP) OUTLET SIDE

FLOW


PLAN VIEW




MAIN PIPE DIA. (IN)	LENGTH A (FT)	SIEVE SIZE	PARTICLE SIZE (CM)	TREATED FLOW RATE (CFS)	INLET Ø (IN)	OUTLET Ø (IN)	OUTLET ORIFICE Ø (IN)
36	20	140	0.0107	1.50	10	10	6.6
36	20	200	0.0076	0.74	10	10	4.7
36	40	140	0.0107	3.08	10	10	9.6
36	40	200	0.0076	1.54	10	10	6.8

STRUCTURE OPTIONS

- FITTING DIMENSIONS VARY WITH UNIT DESIGN, DIMENSIONS CAN BE PROVIDED ONCE DESIGN IS EVALUATED.
- OTHER STRUCTURES MAY BE USED.



<u>INLET STRUCTURE</u> FABRICATED SUMP BASIN OUTLET FABRICATED REDUCING WYE



NOTES:

- 1. SEE STANDARD DETAILS D-4-100 & D-4-101 FOR STORM WATER QUALITY UNIT PRODUCT DETAILS
- 2. CUSTOM UNITS ARE AVAILABLE, CONTACT YOUR PRINSCO SALES REPRESENTATIVE FOR MORE INFORMATION.
- 3. SEE PRINSCO SWQU INSTALLATION GUIDE FOR PROPER INSTALLATION OF PRODUCTS
- 4. FABRICATED TO ASTM F2737 FOR CORRUGATED HDPE WATER QUALITY UNITS.

THIS DETAIL DEPICTS RECOMMENDED INSTALLATION PRACTICES AND IS NOT INTENDED TO SUPERSEDE ANY NATIONAL, STATE OR LOCAL SPECIFICATIONS. PRINSCO BEARS NO RESPONSIBILITY FOR ANY ALTERATIONS, REVISION AND/OR DEVIATION FROM THIS STANDARD DETAIL. PRINSCO HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICE FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION TO VERIFY SUITABILITY. @ PRINSCO, INC.



1717 16TH ST. NE WILLMAR, MN 56201 www.prinsco.com

TITLE:	36"	STORM	IWATE	ER QUALIT	Y UNIT (SWQU)
DRAWN		NJW	DATE:	11-Aug-23	DRAWING NUMBER:
SCALE:		NITO	SHEET:	1 OF 1	↑ D-4-110